

CONSTRUCTION MANUAL



CONNECTICUT DEPARTMENT OF TRANSPORTATION

**BUREAU OF ENGINEERING AND HIGHWAY
OPERATIONS**

OFFICE OF CONSTRUCTION

~ Version 1.2, April 2006 ~

Table of Contents

Chapter 1 – Inspection Rev.

1-100	General.....	1-1.1	
1-101	Scope of the Work	1-1.1	
1-102	Initiating Inspection	1-1.1	
1-103	The Inspector	1-1.2	
1-104	Time on Project.....	1-1.2	
1-105	Address of Inspectors.....	1-1.2	
1-106	Enforcing the Provisions of the Contract.....	1-1.3	
1-107	Safety	1-1.3	
1-108	Change in Travelway Clearances and Bridge Capacity Ratings	1-1.4	
1-109	Data, Supplies and Equipment.....	1-1.4	Dec. 2005

Chapter 2 – Project Initiation

1-201	Project Start Up.....	1-2.1	
1-202	Preconstruction Meetings.....	1-2.1	Dec. 2005
1-203	EEO Preconstruction Meeting	1-2.2	
1-204	Utility Meeting.....	1-2.2	
1-205	Notification of Contract Status	1-2.3	
1-206	Start and Completion Dates for Utilities.....	1-2.4	April 2006

Chapter 3 – Project Documentation

1-301	Reports and Records	1-3.1	Dec. 2005
1-302	Project Correspondence	1-3.2	Dec. 2005
1-303	Email	1-3.2	
1-304	Progress Meetings	1-3.2	Dec. 2005
1-305	Daily Work Report and Diary	1-3.3	Dec. 2005
1-306	Review of DWRs	1-3.6	
1-307	Daily Paving Reports	1-3.7	Dec. 2005
1-308	Computations and Measurements	1-3.7	
1-309	Accuracy of Measurements and Computations	1-3.8	

1-310	Electronic Forms	1-3.8	
1-311	Field Records Format.....	1-3.9	
1-312	Volume I—Diaries and Inspector's Daily Work Reports	1-3.10	
1-313	Volume II—Contract Items (Non-SiteManager Only)	1-3.11	
1-314	Volume III—Computations, Etc.....	1-3.15	
1-315	Volume IV—Miscellaneous Contract Data.....	1-3.15	Dec. 2005
1-316	White Paper Plans	1-3.27	
1-317	Other Project Booklets and Folders	1-3.27	Dec. 2005
1-318	Drainage Systems.....	1-3.28	
1-319	Structures, Mainline Roadway, Ramps, Etc	1-3.30	
1-320	Trafficperson Item	1-3.31	
1-321	Barricade Warning Lights.....	1-3.33	
1-322	Water Pollution Control.....	1-3.33	
1-323	Non-Compliance Notices.....	1-3.34	
1-324	Recycling of Construction Materials	1-3.37	
1-325A	Working Drawings for Permanent Construction	1-3.38	
1-325B	Working Drawings for Temporary Construction.....	1-3.39	
1-325C	Examples of Working Drawings that requires a review by the Office of Engineering	1-3.39	
1-326	Shop Drawings	1-3.39	
1-327	Final Revisions of Plans and Cross Sections (As-Builts)	1-3.40	
1-328	Retention of Project Records	1-3.42	

Chapter 4 – Materials Testing (Preliminary Draft) ***Dec. 2005***

1-401	<i>Overall Responsibilities.....</i>	1-4.1
1-401A	<i>District Construction (Designated Representative).....</i>	1-4.1
1-401B	<i>Division of Materials Testing (Designated Representative).....</i>	1-4.1
1-402	<i>Standard Procedures</i>	1-4.2
1-402A	<i>Request-for-Test Material Control</i>	1-4.2
1-402B	<i>Test Results</i>	1-4.3
1-402C	<i>Samples Recommended for Rejection</i>	1-4.5
1-403	<i>Non-standard Testing Procedures.....</i>	1-4.5
1-404	<i>Minimum Testing Requirements Acceptance and Assurance</i>	1-4.5

<i>1-404A</i>	<i>General</i>	<i>1-4.5</i>	
<i>1-404B</i>	<i>Assurance Samples and Tests</i>	<i>1-4.6</i>	
<i>1-405</i>	<i>Request for Materials Test (Form MAT-100)</i>	<i>1-4.7</i>	
<i>1-406</i>	<i>Request for Materials Test by Telephone</i>	<i>1-4.8</i>	<i>Dec. 2005</i>
<i>1-407</i>	<i>Specialty and Proprietary Items</i>	<i>1-4.9</i>	
<i>1-407A</i>	<i>Certified Test Report</i>	<i>1-4.10</i>	
<i>1-407B</i>	<i>Materials Certificate</i>	<i>1-4.10</i>	
<i>1-407C</i>	<i>Final Material Certification (FMC)</i>	<i>1-4.11</i>	

Chapter 5 – Adjustment of Contract Items & Differing Site Conditions

<i>1-501</i>	<i>Minor Items – Article 1.04.02</i>	<i>1-5.1</i>	
<i>1-501A</i>	<i>Increases of more than 25%</i>	<i>1-5.1</i>	
<i>1-501B</i>	<i>Decreases of more than 25%</i>	<i>1-5.1</i>	
<i>1-501C</i>	<i>Examples of Minor Item Adjustment Situations</i>	<i>1-5.1</i>	
<i>1-502</i>	<i>Change in Quantities of Major Items and Significant Changes in the Character of Work – Article 1.04.03</i>	<i>1-5.2</i>	
<i>1-502A</i>	<i>Examples of Major Item Adjustment Situations:</i>	<i>1-5.3</i>	
<i>1-503</i>	<i>Differing Site Conditions – Article 1.04.04</i>	<i>1-5.3</i>	
<i>1-503A</i>	<i>"TYPE I" Differing Site conditions</i>	<i>1-5.4</i>	
<i>1-503B</i>	<i>"TYPE II" Differing Site conditions</i>	<i>1-5.5</i>	
<i>1-503C</i>	<i>Definitions</i>	<i>1-5.6</i>	
<i>1-503D</i>	<i>Examination of Site Clauses</i>	<i>1-5.7</i>	
<i>1-504</i>	<i>Adjusted Price Forms for Major Items, Change in Character of Work & Different Site Conditions</i>	<i>1-5.7</i>	<i>Dec. 2005</i>

Chapter 6 – Extra and Cost-Plus Work

<i>1-600</i>	<i>General</i>	<i>1-6.1</i>	
<i>1-601</i>	<i>Agreed Price</i>	<i>1-6.1</i>	<i>Dec. 2005</i>
<i>1-602</i>	<i>Cost Plus</i>	<i>1-6.2</i>	<i>April 2006</i>
<i>1-602A</i>	<i>Labor Rates</i>	<i>1-6.4</i>	
<i>1-602B</i>	<i>Labor Markup for Insurance and Taxes and Bonding</i>	<i>1-6.6</i>	<i>Dec. 2005</i>
<i>1-602C</i>	<i>Specialized Work</i>	<i>1-6.6</i>	

1-602D	Plant Openings during Winter Shutdown	1-6.6	Dec. 2005
1-602E	Rental Rate Blue Book™.....	1-6.7	Dec. 2005
1-602F	Idle Equipment.....	1-6.7	
1-602G	Rented Equipment.....	1-6.8	Dec. 2005

Chapter 7 – Time Extensions & Suspensions

1-701	Documentation of Delays and Effect on Project.....	1-7.1	
1-702	Time Extensions Procedures.....	1-7.1	
1-702A	Time Extension Authority.....	1-7.1	
1-702B	Time Extension Requests.....	1-7.1	
1-702C	Time Extension Analysis	1-7.2	
1-702D	Federal Agency Approval.....	1-7.3	
1-702E	Assistant District Engineer Approval/Disapproval.....	1-7.3	
1-703	Temporary Suspensions and Resumptions	1-7.6	

Chapter 8 – Construction Orders

1-800	General.....	1-8.1	
1-801	Review of Proposed Changes	1-8.1	
1-802	Need for Construction Orders	1-8.2	
1-803	Construction Order Preparation	1-8.2	Dec. 2005
1-804	Federal Oversight Projects.....	1-8.2	Dec. 2005
1-805	Content.....	1-8.3	Dec. 2005
1-806	Standard Explanations - Classification of Line Item Changes	1-8.6	
1-807	Documentation.....	1-8.8	
1-808	General Processing Guidelines	1-8.8	Dec. 2005
1-809	Review and Processing Procedure	1-8.9	Dec. 2005
1-809A	Review by Project Engineer.....	1-8.10	
1-809B	Review by Supervising Engineer.....	1-8.10	
1-809C	Authorization to Process Construction Order (<i>New</i>)	1-8.10	Dec. 2005
1-809D	Review and Initial Processing by District (<i>formerly 1-809C</i>)	1-8.11	
1-809E	Processing by Project Engineer (<i>formerly 1-809D</i>).....	1-8.11	
1-810	Guidelines for Approval of Construction Orders.....	1-8.12	Dec. 2005

1-810A	Final Processing by District.....	1-8.13	Dec. 2005
1-810B	Distribution	1-8.13	Dec. 2005
1-811	Final Construction Orders.....	1-8.13	

Chapter 9 – Contract Payments

1-901	Progress Estimates	1-9.1	Dec. 2005
1-902	Estimate Period	1-9.1	
1-903	Estimate Preparation and Review	1-9.3	
1-904	Funds.....	1-9.4	Dec. 2005
1-905	Retainage and Securities	1-9.4	Dec. 2005
1-906	Extra or Additional Work	1-9.5	Dec. 2005
1-907	Liquidated Damages, Sanctions, and Item Adjustments	1-9.5	
1-908	Deductions	1-9.5	
1-909	Lump Sum Items.....	1-9.6	
1-910	Payment for Stored Materials	1-9.6	Dec. 2005
1-911	Payment to Subcontractors and Suppliers.....	1-9.9	
1-912	Credits due State	1-9.10	Dec. 2005

Chapter 10 – Contract Completion

April 2006

1-1000	General.....	1-10.1	
1-1001	Opening to Traffic or Occupancy	1-10.1	
1-1002	Semifinal Inspection	1-10.1	
1-1003	Notice of Substantial Completion and Stopping Contract Time	1-10.2	
1-1004	Final Inspection.....	1-10.3	
1-1004A	Partial Final Inspection & Partial Relief of Responsibility	1-10.3	
1-1005	Termination of Contractor's Responsibilities & Certificate of Acceptance of Work	1-10.3	
1-1006	Form FHWA-47—Statement of Materials and Labor Used.....	1-10.5	
1-1007	District and Headquarters Final Review	1-10.10	
1-1008	Checks to Final a Project	1-10.10	
1-1009	Final Estimates.....	1-10.11	

1-1010	Acceptance of Contract.....	1-10.11
1-1011	Final Papers.....	1-10.13
1-1012	Consultant-Inspected Project	1-10.21
1-1013	Storage of Revised Plans and Notebooks	1-10.21

Chapter 11 – Guidelines for the District and Headquarters Intermediate and Final Reviews

1-1101	Intermediate and Final Review	1-11.1
1-1101A	Items.....	1-11.2
1-1101B	Volume I – Inspector’s Daily Work Report.....	1-11.3
1-1101C	Volume III – Computations	1-11.3
1-1101D	Volume IV – Miscellaneous Contract Data	1-11.4
1-1102	Emergency Cost-Plus Projects.....	1-11.5
		Dec. 2005

Chapter 12 – Civil Rights

1-1201	Subcontracts	1-12.1
1-1202	Labor Compliance.....	1-12.1
1-1202A	Statements and Payrolls	1-12.2
1-1202B	Salaried Employees.....	1-12.4
1-1202C	Wage Rate Checks	1-12.5
1-1202D	Project Payroll / Wage Check Monthly Summary.....	1-12.8
1-1202E	Processing Complaints or Violations.....	1-12.9
1-1203	Equal Employment Opportunity and Affirmative Action	1-12.11
1-1204	DBE Goal or SBE Set-Aside Goal Contract Participation	1-12.17
1-1205	DBE and SBE Reports	1-12.18
1-1205A	Quarterly Contractor Reports.....	1-12.18
1-1205B	Quarterly Consultant Reports and Subconsultant Reports.....	1-12.18
1-1205C	Final DBE/SBE Reports	1-12.21
1-1206	DBE or SBE Fulfillment and Shortfall Procedure	1-12.22
1-1207	On-the-Job Training.....	1-12.24
1-1207A	Contractor Preconstruction Requirements	1-12.25
1-1207B	Trainee Monitoring	1-12.27

1-1208	Freedom of Information.....	1.12.32
--------	-----------------------------	---------

Chapter 13 – Utilities (*Preliminary Draft*)

1-1300	<i>General</i>	1-13.1
1-1301	<i>Design Phase</i>	1-13.1
1-1302	<i>Preconstruction Phase</i>	1-13.1
1-1303	<i>Construction Phase</i>	1-13.2
1-1303A	<i>Utility Coordination</i>	1-13.2
1-1303B	<i>Inspection and Record Keeping</i>	1-13.2
1-1303C	<i>Review and Signature of CON 40's and CON 41's</i>	1-13.3
1-1303D	<i>Change in Scope and Cost Overrun Requests</i>	1-13.4

Chapter 14 – Project Incidents and Complaint

1-1401	Reporting Complaints and Damage or Injury Claims.....	1-14.1
1-1402	Telephone Complaints	1-14.1
1-1403	Property Owner Complaints	1-14.2
1-1404	Improprieties	1-14.2
1-1405	Motorist Claims	1-14.2
1-1406	Other Property Damage and Personal Injury Claims.....	1-14.5
1-1407	Claims Against the State.....	1-14.5
1-1408	Claims Against the Contractor.....	1-14.6
1-1409	Prompt Payment Complaints	1-14.6
1-1410	Major Project Incident	1-14.8
1-1411	Report of Burglary, Theft, or Vandalism of State-Owned Property	1-14.11

Chapter 15 – Disputes & Claims

1-1501	Contractor's Right to Claim.....	1-15.1
1-1502	Notification Requirements	1-15.1
1-1503	The Dispute & Claim Process.....	1-15.2

Chapter 16 – Design Error Procedure**April 2006**

1-1600	General.....	1-16.1
1-1601	Construction Issues Form	1-16.1
1-1601A	The District responsibilities are as follows:.....	1-16.1
1-1601B	The Office of Construction's responsibilities is as follows:.....	1-16.1
1-1602	Active Claim by Contractor	1-16.3

Chapter 17 – Consultant Engineers

1-1701	Consultant Evaluations	1-17.1
1-1702	Bi-Monthly Evaluation of Consultant's Performance Guide.....	1-17.1
1-1703	Semi-annual Consultant Evaluation Procedures.....	1-17.1

Chapter 18 – Emergency Projects**Dec. 2005**

1-1800	General.....	1-18.1
1-1801	Case 1 Initiation Procedure (Office of Construction).....	1-18.1
1-1802	Case 1 Emergency Projects (District)	1-18.3
1-1803	Volume I – Inspector's Daily Work Reports	1-18.5
1-1804	Volume III – Cost-Plus (CON-9) Sheets	1-18.5
1-1805	Volume IV	1-18.6

Chapter 19 – Insurance and Bond Requirements

1-1901	Insurance Requirements.....	1-19.1
1-1902	Performance Bonds.....	1-19.4

Chapter 20 – M&PT Changes and Public Relations**April 2006**

1-2000	General.....	1-20.1
1-2001	Procedures for Revising Contract Provisions for M&PT	1-20.1
1-2001A	Case 1 – Revision to Contract Traffic Staging Plans.....	1-20.1
1-2001B	Case 2 – Revision to Limitation of Operations, and Prosecution and Progress Provisions	1-20.2
1-2001C	Case 3 – Emergency Operations	1-20.2
1-2002	Press Release Procedures	1-20.3

Chapter 21 – Municipal Systems Oversight Procedures

April 2006

1-2100	General.....	1-21.1
1-2101	MSAT Responsibilities.....	1-21.1
1-2102	Design/Constructibility Reviews	1-21.1
1-2103	Preliminary Meeting with the Municipality.....	1-21.2
1-2104	Municipal Setup for SiteManager Information.....	1-21.6
1-2105	Municipal Preconstruction Meeting.....	1-21.7
1-2106	Municipal Testing Procedures	1-21.7
1-2107	Municipal CON 100s	1-21.8
1-2108	CLA 3s for Projects performed by Contractor/Consultant	1-21.8
1-2109	CLA3's for Projects performed by Municipal Force Account	1-21.9
1-2110	Change In Scope Approval Process.....	1-21.10
1-2111	Municipality Construction Orders	1-21.10
1-2112	Claim Procedures	1-21.11
1-2113	Periodic Records Review.....	1-21.11
1-2114	Semifinal And Final Inspection	1-21.14
1-2115	Closing Out Projects	1-21.16
1-2116	Submission of Finals Package to Office of Construction	1-21.16

Appendix A – SiteManager Project Inspection Manual

Appendix B – Update Procedures

B-100	General.....	B-1.1
B-101	Responsibilities.....	B-1.1
B-102	Construction Manual Panel.....	B-1.1
B-103	Construction Manual Coordinator	B-1.1
B-104	Types of Changes.....	B-1.3
B-105	Sources of Changes.....	B-1.4
B-106	Procedures for Making Changes to Construction Manual	B-1.4
B-107	Suggesting Revision to the Standard Specifications.....	B-1.5

Dec. 2005

List of Figures

Figure 1-2.1 Contract Status (Form CON-100)	1-2.4	
Figure 1-3.1 Sample of Report of Meeting.....	1-3.4 & 1-3.5	
Figure 1-3.2 Accuracy of Measurements and Computations.....	1-3.8	
Figure 1-3.3 Volume II - Project Identification/Construction Recordkeeping Format Sheet.....	1-3.11	
Figure 1-3.4 Volume II - Construction Item Index.....	1-3.12	
Figure 1-3.5 Volume II - Request for Test Index	1-3.13	
Figure 1-3.6 Volume II - Contract Item Page	1-3.14	
Figure 1-3.7 Volume II - Contract Item Testing Data Page	1-3.14	
Figure 1-3.8 Volume III – Sample Item Summary Sheet	1-3.16	
Figure 1-3.9 Volume III – Sample Master Summary Sheet	1-3.16	
Figure 1-3.10 Volume IV – Sample Volume IV Index	1-3.17	Dec. 2005
Figure 1-3.11 Volume IV – Inspection of Field Records by Supervisory Personnel	1-3.18	
Figure 1-3.12 Volume IV – Record of Equipment Used.....	1-3.18	
Figure 1-3.13 Volume IV – Record of Prime Contractors and Subcontractors.....	1-3.19	
Figure 1-3.14 Volume IV – Record of Insurance and Bonding Companies.....	1-3.19	
Figure 1-3.15 Volume IV – Record of Construction Orders	1-3.20	
Figure 1-3.16 Volume IV – Index of Construction Orders.....	1-3.21	
Figure 1-3.17 Volume IV – Record of State Furnished Materials.....	1-3.21	Dec. 2005
Figure 1-3.18 Volume IV – Work Performed by Others.....	1-3.22	Dec. 2005
Figure 1-3.19 Volume IV – Record of State/Consultant Personnel...	1-3.22	
Figure 1-3.20 Volume IV – Record of Labor Wage Checks	1-3.23	
Figure 1-3.21 Volume IV – Record of Certified Payrolls	1-3.23	
Figure 1-3.22 Volume IV – Record of Transfer Vouchers.....	1-3.24	Dec. 2005
Figure 1-3.23 Volume IV – “MATERIAL STORED” INVENTORY LOG	1-3.24	
Figure 1-3.24 Volume IV – Record of Shop Drawings and Working Drawings.....	1-3.24	

Figure 1-3.25 Volume IV – Record of Activity 06.....	1-3.25	
Figure 1-3.26 Volume IV – Project Payroll/Wage Check Monthly Summary	1-3.26	
Figure 1-3.27 Volume III – Drainage Master Summary Log	1-3.28	
Figure 1-3.28 Volume III – Drainage (Right-Hand Page).....	1-3.29	
Figure 1-3.29 Volume III – Drainage (Left-Hand Page)	1-3.29	
Figure 1-3.30 Volume III – Index Sheet.....	1-3.30	
Figure 1-3.31 Volume III – Item Master Summary	1-3.31	
Figure 1-3.32 Volume III – Flasher Summary.....	1-3.33	
Figure 1-3.33 Volume III – Water Pollution Control Summary.....	1-3.34	
Figure 1-3.34 Part “A” Non-Compliance Notice.....	1-3.35	
Figure 1-3.35 Part “B” Compliance Notice	1-3.36	
Figure 1-3.36 Type Designation of Recycled Material	1-3.37	
Figure 1-3.37 Recycling Report.....	1-3.38	
Figure 1-4.1 Request for Test (Form MAT-100	1-4.3	
Figure 1-4.2 Request for Test (Form MAT-100) SiteManager	1-4.4	
Figure 1-5.1 Adjusted Price (No Equipment Audit)	1-5.8	Dec. 2005
Figure 1-5.2 Adjusted Price (Equipment Audit)	1-5.8	Dec. 2005
Figure 1-6.1 Sample Estimate for Cost Plus Work.....	1-6.3	Dec. 2005
Figure 1-6.1 Daily Report of Cost Plus, Form CON 9(formerly 1-6.2)	1-6.5	Dec. 2005
Figure 1-7.1 Sample Letter Project Engineer Time Extension Response	1-7.2	
Figure 1-7.2 Time Extension Approval/Disapproval Memorandum....	1-7.4	
Figure 1-7.3 Sample Letter to FHWA Requesting Concurrence with Time Extension	1-7.5	
Figure 1-8.1 Sample Estimate for Cost Plus Work.....	1-8.5	Dec. 2005
Figure 1-8.2 Table of Standard Change Order Explanation IDs	1-8.6 & 1-8.7	
Figure 1-8.3 Construction Order Routing Slip	1-8.9	
Figure 1-8.4 Second Letter to Contractor Transmitting Construction Order	1-8.12	
Figure 1-8.5 Distribution of Construction Order Copies	1-8.14	Dec. 2005
Figure 1-9.1 Payment Estimate.....	1-9.1 – 1-9.3	
Figure 1-9.2 Certificate of Title Sample Form	1-9.7 & 1-9.8	Dec. 2005

Volume 1**Contract Administration**

Figure 1-10.1 Certificate of Acceptance of Work (Form CON-500) 1-10.4	Dec. 2005
Figure 1-10.2 Vacant	
Figure 1-10.3a Form FHWA-47	1-10.6 Dec. 2005
Figure 1-10.3b Form FHWA-47 Instructions.....	1-10.7 Dec. 2005
Figure 1-10.3c Form FHWA-47M.....	1-10.8 Dec. 2005
Figure 1-10.3d Form FHWA-47 Instructions.....	1-10.9 Dec. 2005
Figure 1-10.4 Certificate of Acceptance of Project (Form CON-501) 1-10.12	Dec. 2005
Figure 1-10.5 Final Transmittal Memorandum.....	1-10.13 Dec. 2005
Figure 1-10.6 Table for No. of Attachments for Final Transmittal Memorandum	1-10.14 Dec. 2005
Figure 1-10.7a-b Construction Report.....	1-10.15 &1-10.16 Dec. 2005
Figure 1-10.8 Financial Summary Checklist	1-10.17 Dec. 2005
Figure 1-10.9 Project Cost Overrun Report	1-10.18 Dec. 2005
Figure 1-10.10a-b Pavement Evaluation Form	1-10.19 &1-10.20 Dec. 2005
Figure 1-12.1 Certified Payroll.....	1-12.3
Figure 1-12.2 Certified Payroll / State Statement of Compliance	1-12.3
Figure 1-12.3 Certified Payroll / Federal Statement of Compliance .	1-12.4
Figure 1-12.4 CT DOL Apprenticeship Registration Agreement.....	1-12.6
Figure 1-12.5 Labor Wage Check (Form CON-131).....	1-12.7
Figure 1-12.6 Prevailing Wage Referral Form	1-12.8
Figure 1-12.7 Project Payroll / Wage Check Monthly Summary....	1-12.10
Figure 1-12.8 Construction Project Site Record Review	1-12.12 & 1-12.13
Figure 1-12.9 Sample Letter Project Site Record Review Request Letter	1-12.14 – 1-12.16
Figure 1-12.10 Sample DBE or SBE Quarterly Report.....	1-12.19
Figure 1-12.11 Sample Consultant Quarterly Report	1-12.19
Figure 1-12.12 Subconsultant Payment Log.....	1-12.20
Figure 1-12.13 Final DBE or SBE Participating Report.....	1-12.21
Figure 1-12.14 Sample Letter to Contractor Requesting Documentation to Substantiate DBE (SBE) Payments	1-12-23
Figure 1-12.15 Sample DBE (SBE) Payment Verification	1-12.24
Figure 1-12.16 Trainee Approval Form (Form 1415)	1-12.26

Figure 1-12.17 Trainee Summary	1-12.28	
Figure 1-12.18 Monthly Training Report (Form 1409 – Front)	1-12.28	
Figure 1-12.18 Monthly Training Report (Form 1409 – Back).....	1-12.29	
Figure 1-12.19a-d CT DOL Apprentice Handbook and Progress Record Sample	1-12.29 – 1-12.31	
Figure 1-12.20 Sample Training Payment Recommendation Memo	1-12.31	
Figure 1-14.1 Sample Letter to Contractor Regarding Claim from Motorist	1-14.3	
Figure 1-14.2 Sample Letter to Claimant.....	1-14.4	
Figure 1-14.3 Prompt Payment Complaint Log.....	1-14.6	
Figure 1-14.4 Standard Prompt Payment Letter to Contractor.....	1-14.7	
Figure 1-14.5 Incident Notification Process	1-14.9	Dec. 2005
Figure 1-14.6 Report of Major Road Closure / Project Incident / Emergency Work Form	1-14.10	Dec. 2005
Figure 1-14.7 Report of Burglary, Theft or Vandalism	1-14.12	
Figure 1-16.1 Construction Issues Form.....	1-16.2	April 2006
Figure 1-17.1 Bi-Monthly Consultant Performance Evaluation Rating Form	1-17.2 &1-17.3	
Figure 1-17.2 Semi-Annual Consultant Performance Evaluation Rating Form	1-17.4 & 1-17.5	
Figure 1-18.1 Emergency Project Status Report.....	1-18.4	
Figure 1-19.1 Certificate of Insurance (CON-32).....	1-19.2	
Figure 1-19.2 Sample Letter to Contractor Requesting Evidence of Insurance	1-19.3	
Figure 1-19.3 Sample Letter Requesting New Performance Bond....	1-19.4	
Figure 1-19.4 Sample Performance Bond Rider.....	1-19.5	
Figure 1-20.1 Case 2 Backup Documentation Form	1-20.3	April 2006
Figure 1-20.2 Construction Press Release Flow Chart	1-20.6	April 2006
Figure 1-21.1 Preliminary Meeting / Municipal Projects Check List.....	1-21.3 – 1-21.5	April 2006
Figure 1-21.2 Project Administration Review	1-21.12 & 1-21.13	April 2006
Figure 1-21.3 Sample Letter Transmitting Project Administration Review.	1-21.15	April 2006
Figure B-1 Suggested Revision to Construction Manual Form.....	B-1.2	

Volume 1**Contract Administration**

Figure B-2 List of Revisions.....B-1.3

Figure B-3 Recommended Revision to Standard Specifications Memorandum B-1.6

Table of Contents

Chapter 1 - Environmental Protection

2-100	General	2-1.1
2-101	Permits.....	2-1.1
2-101A	Department of Environmental Protection	2-1.1
2-101B	Army Corps of Engineers.....	2-1.2
2-102	Pollution Control Regulations.....	2-1.2
2-102A	Air Pollution	2-1.2
2-102B	Noise Pollution	2-1.2
2-102C	Water Pollution.....	2-1.2
2-103	Specifications	2-1.2
2-103A	Response to Environmental Deficiencies	2-1.2
2-104	Duties and Responsibilities	2-1.3
2-104A	Inspection Personnel	2-1.3
2-104B	Environmental Inspector	2-1.6
2-104C	District Environmental Coordinator	2-1.6
2-104D	District Office.....	2-1.7
2-104E	Office of Environmental Planning	2-1.7
2-104F	Contractor.....	2-1.7
2-105	Permit Process	2-1.7
2-105A	Department of Environmental Protection.....	2-1.7
2-105B	Army Corps of Engineers.....	2-1.8
2-106	Review of Contract Documents	2-1.8
2-106A	Preconstruction Meeting	2-1.8
2-106B	Site Preparation	2-1.9
2-107	Permit Modifications.....	2-1.9
2-108	Procedure for Requesting Technical Revisions to DEP Permits	2-1.9
2-108A	Regulated Areas.....	2-1.9
2-108B	Non Regulated Areas.....	2-1.10

2-109	Contaminated or Hazardous Materials	2-1.10
2-109A	Known Waste on Site.....	2-1.10
2-109B	Unknown Materials Found on Site.....	2-1.10
2-109C	Emergency Response Procedure for Suspected Contaminated Materials.....	2-1.11
2-109D	Contractor Spills	2-1.12
2-109E	Emergency Response procedure to Contractor Spill	2-1.12
2-110	Structure Painting Debris.....	2-1.12
2-110A	Containment and Collection of Surface Preparation Debris.....	2-1.12
2-110B	Disposal of Hazardous or Contaminated Debris.....	2-1.13
2-110C	Contaminated Debris	2-1.13
2-110D	Hazardous Debris.....	2-1.13
2-110E	Miscellaneous Construction Details.....	2-1.13
2-111	Sedimentation and Erosion Controls	2-1.14
2-111A	Handling Water	2-1.14
2-111B	Dewatering.....	2-1.14
2-111C	Slope Stabilization	2-1.15
2-112	Water Pollution Control	2-1.15
2-112A	Off-Site Locations.....	2-1.15
2-112B	Storage of Materials and Equipment	2-1.15
2-112C	Response to Deficiencies.....	2-1.15
2-113	Contractor Noncompliance.....	2-1.16
2-113A	Department Authority	2-1.16
2-113B	24-Hour Rule	2-1.16
2-113C	24-Hour Rule Form.....	2-1.16
2-113D	Procedure.....	2-1.18
2-114	Reports and Recordkeeping.....	2-1.19
2-114A	Environmental Checklist—New Project Startup	2-1.19
2-114B	Recycling Report for Construction Projects	2-1.20
2-114C	Recordkeeping	2-1.20
2-115	Procedure Relating to Water Resources Authorizations for Emergencies	

Declared By the Connecticut Department of Transportation

Commissioner, May 1,2002 2-1.24

Chapter 2 - Construction Surveys

2-201	Survey Parties.....	2-2.1
2-201A	Responsibilities and Duties of Survey Parties on Construction Projects	2-2.1
2-201B	Responsibility and Duties of Chief of Party	2-2.1
2-201C	Assignment of Survey Parties	2-2.2
2-202	Survey Equipment	2-2.3
2-202A	Assignment of Field Party Equipment.....	2-2.3
2-202B	Use of Equipment.....	2-2.3
2-202C	Transporting Equipment.....	2-2.3
2-202D	Damage to Equipment.....	2-2.3
2-203	Safety and Traffic Control.....	2-2.3
2-204	Note Keeping.....	2-2.4
2-204A	Standard Note Keeping	2-2.4
2-204B	Care of Notebooks.....	2-2.4
2-204C	Survey Notes	2-2.5
2-204D	Notes for Bench Levels	2-2.5
2-204E	Cross Section Note Guidelines	2-2.6
2-204F	Cross Section Notes (Levels and Rods)	2-2.6
2-204G	Notes on Bridge Staking	2-2.7
2-204H	Notes for Construction Stakes.....	2-2.7
2-205	Computations.....	2-2.7
2-205A	Completeness of Computations	2-2.7
2-205B	Revisions to Computations	2-2.7
2-206	Staking	2-2.8
2-206A	Staking Centerline	2-2.8

2-207	Cross Sections	2-2.11
2-207A	Earthwork.....	2-2.11
2-207B	Rock Excavation	2-2.11
2-207C	Unsuitable Material.....	2-2.11
2-207D	Borrow Banks	2-2.12
2-207E	Stakes for Concrete and Other High Type Pavements	2-2.12
2-207F	Staking Bridge Structures	2-2.12
2-207G	Staking Special Structures	2-2.13
2-208	Replacing Stakes	2-2.13
2-209	Measurements for Monthly Estimates.....	2-2.13
2-210	Final Survey	2-2.14

Chapter 3 - Excavation and Embankment

2-300	General	2-3.1
2-300A	Introduction.....	2-3.1
2-300B	Definitions.....	2-3.1
2-301	Setting Slope Stakes.....	2-3.1
2-302	Clearing and Grubbing	2-3.2
2-302A	Description.....	2-3.2
2-302B	Preliminary Activities	2-3.3
2-302C	Tree Removal and Protection	2-3.4
2-302D	Disposing of Materials.....	2-3.4
2-302E	Disposal Outside the Highway Limits	2-3.4
2-302F	Disposal Inside the Highway Limits	2-3.4
2-302G	Areas Outside Roadway Limits But Within Highway Taking Lines.....	2-3.5
2-303	Survey Markers and Monuments	2-3.5
2-304	Excavation and Embankment	2-3.5
2-304A	Definitions.....	2-3.5

2-304B	Earth Excavation	2-3.6
2-304C	Excavation Procedure.....	2-3.6
2-305	Rock Excavation.....	2-3.7
2-305A	Determining the Quantity To Be Removed	2-3.7
2-305B	Blasting Safety Meeting.....	2-3.7
2-305C	Presplitting Rock Slopes	2-3.8
2-306	Blasting Regulations and Good Practices	2-3.8
2-306A	Regulations	2-3.8
2-306B	Transport and Storage.....	2-3.8
2-306C	Warnings	2-3.8
2-306D	Special Precautions	2-3.9
2-306E	Normal Operations	2-3.10
2-306F	Record Keeping.....	2-3.10
2-306G	Operations.....	2-3.10
2-306H	Payment	2-3.11
2-307	Surplus and Unsuitable Material.....	2-3.11
2-308	Surplus Material	2-3.11
2-309	Unsuitable Material	2-3.11
2-309A	General.....	2-3.11
2-309B	Top Soil.....	2-3.12
2-309C	Use or Disposal of Material	2-3.12
2-311	Salvageable Material.....	2-3.13
2-312	State's Property	2-3.14
2-313	Contractor's Property	2-3.14
2-314	Use of Reclaimed Waste Materials on Construction Projects	2-3.14
2-315	Conditions Requiring Corrective Work	2-3.14
2-316	Embankment Building	2-3.15
2-316A	General.....	2-3.15
2-316B	Borrow	2-3.15
2-316C	Corrections	2-3.15
2-317	Monthly Pay Quantities.....	2-3.16

2-318	Final Pay Quantities.....	2-3.16
2-319	Winter Embankment Operations	2-3.17
2-320	Embankment Density.....	2-3.17
2-320A	Field Sampling for Proctor Determinations	2-3.17
2-320B	Field Density Test Equipment	2-3.18
2-320C	Field Density Test Procedures and Steps.....	2-3.18
2-321	Water Pollution	2-3.19
2-321A	Sedimentation Control Plan.....	2-3.19
2-321B	Responsibilities	2-3.19
2-321C	Operations	2-3.19
2-322	Call Before You Dig.....	2-3.21
2-322A	Utility Warning Tapes	2-3.21
2-322B	Reporting.....	2-3.22

Chapter 4 - Drainage

2-400	General	2-4.1
2-401	Purpose	2-4.1
2-402	Outlets	2-4.2
2-403	Natural Water Course.....	2-4.2
2-404	Drainage Right-of-Way.....	2-4.2
2-405	Right-to-Drain.....	2-4.2
2-406	Adverse Rights.....	2-4.2
2-407	Agreements	2-4.3
2-408	Runoff Design	2-4.3
2-409	Trench Excavation	2-4.3
2-409A	General	2-4.3
2-409B	Rock Excavation	2-4.4
2-409C	Backfilling.....	2-4.4
2-410	Foundations.....	2-4.4

2-411	Culverts.....	2-4.4
2-412	Types of Culverts.....	2-4.5
2-412A	Corrugated Metal Pipe	2-4.5
2-412B	Plate Pipes and Arches	2-4.5
2-412C	Concrete Pipe.....	2-4.6
2-413	Pipe Selection	2-4.6
2-413A	General Guidelines.....	2-4.6
2-413B	Available Metal Pipe	2-4.7
2-413C	Concrete Pipe Strength.....	2-4.7
2-413D	Loading	2-4.7
2-414	Materials Inspection	2-4.7
2-414A	Corrugated Metal Pipe	2-4.8
2-414B	Concrete Pipe.....	2-4.8
2-415	Culvert and Endwall Layout	2-4.10
2-415A	General Method.....	2-4.10
2-415B	Field Method	2-4.10
2-416	Trench Excavation.....	2-4.12
2-417	Foundations	2-4.12
2-418	Culvert Installation.....	2-4.12
2-418A	Corrugated Metal Pipe	2-4.13
2-418B	Plate Pipe and Arches	2-4.14
2-418C	Concrete Pipe.....	2-4.15
2-419	Backfilling	2-4.15
2-420	Drainage Structures	2-4.15
2-420A	Materials Inspection of Precast Units	2-4.15
2-420B	Culvert End Treatment	2-4.16
2-420B.1	Endwalls	2-4.16
2-420B.2	End Sections	2-4.16
2-420B.3	Endwall Improvements	2-4.16
2-420C	Box Culverts.....	2-4.17
2-420D	Catch Basins and Drop Inlets.....	2-4.17

2-420D.1	New Construction	2-4.17
2-420D.2	Resetting Catch Basins	2-4.17
2-420E	Manholes	2-4.19
2-421	Underdrains	2-4.19
2-421A	Subsurface Drainage Systems	2-4.19
2-421B	Excavation and Installation	2-4.21
2-421C	Backfilling	2-4.21
2-422	Ditches and Channels	2-4.21

Chapter 5 - Base Courses

2-501	Subgrade	2-5.1
2-501A	General	2-5.1
2-501B	Construction Method	2-5.1
2-501C	Payment	2-5.1
2-502	Subbase	2-5.2
2-502A	General	2-5.2
2-502B	Construction Method	2-5.2
2-502C	Payment	2-5.6
2-503	Base Courses	2-5.6
2-504	Rolled Granular Base	2-5.6
2-504A	General	2-5.6
2-504B	Construction Method	2-5.6
2-504C	Payment	2-5.7
2-505	Processed Aggregate Base	2-5.7
2-505A	General	2-5.7
2-505B	Construction Method	2-5.7
2-505C	Payment	2-5.8
2-506	Bituminous Concrete Class 4	2-5.8
2-507	Concrete Base	2-5.8

Chapter 6 - Bituminous Pavements

2-601	Bituminous Concrete Pavement.....	2-6.1
2-601A	General.....	2-6.1
2-602	Bituminous Concrete Classes and Applications	2-6.1
2-603	Contract Specifications	2-6.2
2-604	Contract Plans.....	2-6.2
2-605	Production Responsibility	2-6.2
2-606	Inspection Responsibilities.....	2-6.3
2-606A	Central Laboratory	2-6.3
2-606B	District Responsibilities	2-6.3
2-606C	Preliminary Inspection and Approval of Plant	2-6.3
2-607	Inspection Prior to Paving	2-6.3
2-607A	Paving Equipment	2-6.3
2-607B	Paving Machines	2-6.4
2-607C	Rollers.....	2-6.7
2-607D	Material Transfer Device (MTD).....	2-6.8
2-607E	Lighting	2-6.8
2-608	Base Preparation.....	2-6.9
2-609	Utilities	2-6.10
2-610	Prepaving Meeting	2-6.10
2-611	Test Section.....	2-6.13
2-612	Traffic Control	2-6.13
2-613	Inspection During Paving.....	2-6.13
2-613A	The Day Before	2-6.13
2-613B	Transportation of Mixture	2-6.14
2-613C	Paving Inspection	2-6.14

2-614	Tack Coat	2-6.15
2-615	Mechanical Spreading	2-6.17
2-615A	Screed Unit.....	2-6.17
2-615B	Angle of Attack	2-6.18
2-615C	Head of Material	2-6.19
2-615D	Paving Speed.....	2-6.20
2-615E	Other Factors.....	2-6.20
2-616	Hand Spreading.....	2-6.21
2-617	Delays or Shutdowns	2-6.21
2-618	Thickness and Tonnage Control	2-6.31
2-619	Determining Planned Rate of Spread	2-6.32
2-620	Depth and Yield Checks	2-6.32
2-620A	Depth Checks	2-6.32
2-620B	Yield Checks	2-6.32
2-620C	Inspector Responsibility	2-6.33
2-620D	Stationing	2-6.33
2-620E	Computing Actual Rates of Spread	2-6.33
2-621	Compaction	2-6.36
2-621A	Rolling.....	2-6.36
2-621B	Initial or Breakdown Rolling.....	2-6.37
2-621C	Intermediate Rolling	2-6.38
2-621D	Final Rolling	2-6.38
2-622	Compaction Testing	2-6.39
2-623	Transverse Joints.....	2-6.39
2-624	Permanent Transitions	2-6.39
2-625	Permanent Transitions at Structures	2-6.39
2-626	Temporary Transitions	2-6.39
2-627	Longitudinal Joints	2-6.45
2-628	Paving Adjacent Lanes	2-6.46
2-629	Surface Tolerance.....	2-6.46
2-630	Pavement Smoothness (Rideability)	2-6.46

2-631	Semi-final and Final Inspection	2-6.47
2-632	Opening to Traffic	2-6.47
2-633	Records	2-6.47
2-633A	Form MAT-7	2-6.47
2-633B	Weekly HMA Production Report.....	2-6.50
2-633C	Inspectors Report.....	2-6.51
2-633D	Weigh Tickets	2-6.54
2-634	Test Frequencies	2-6.55
2-635	District Monitoring.....	2-6.55
2-636	Legal Load Limits and Oversize/Overweight Permit Regulations	2-6.55
2-637	Asphalt (HMA) Adjustment Procedures	2-6.55
2-637A	HMA Overweight Adjustment (tons)	2-6.56
2-637B	Material Deficiency Adjustment (dollars).....	2-6.56
2-637C	HMA Density Adjustment (dollars).....	2-6.56
2-637D	Rideability Adjustment (dollars)	2-6.56
2-637E	Measured Weight Adjustment (tons)	2-6.56
2-637F	Liquid Asphalt Adjustment (dollars)	2-6.56
2-638	Pavement Rehabilitation	2-6.60
2-638A	General.....	2-6.60
2-638B	Inspection of Work Site Before Work Commences.....	2-6.60
2-638C	Inspection of Existing Pavement Repairs Prior to Overlay.....	2-6.61
2-638D	Repairs to Existing Bituminous Pavement	2-6.61
2-638D.1	Crack Sealing.....	2-6.62
2-638D.2	Alligatedored Pavement Repair	2-6.62
2-638D.3	Pothole Repair	2-6.62
2-638D.4	Leveling or Milling	2-6.62
2-638E	Repairs to Existing Concrete Pavements.....	2-6.63
2-638E.1	Partial Depth Patch Repair	2-6.63
2-638E.1a	Preparations	2-6.63
2-638E.1b	Tacking	2-6.46
2-638E.1c	Repairs	2-6.65

2-638E.2	Full-Depth Concrete Pavement Replacement.....	2-6.65
2-638E.2a	Subbase and Subgrade Preparation	2-6.65
2-638F	Bituminous Concrete Overlay	2-6.66
2-639	Bituminous Concrete Lip Curbing	2-6.66
2-639A	General	2-6.66
2-639B	Machine Construction.....	2-6.66
2-639C	Hand Construction	2-6.67
2-639D	Bituminous Concrete Driveway Aprons	2-6.67
2-639E	Precautions.....	2-6.67

Chapter 7 - Concrete Pavements

2-701	New Pavement	2-7.1
2-702	Specifications and Plans	2-7.1
2-702A	Specifications.....	2-7.1
2-702B	Plans	2-7.1
2-703	Inspection Team	2-7.2
2-704	Mix Request.....	2-7.2
2-705	Materials Control	2-7.2
2-706	Batching and Mixing Equipment	2-7.4
2-707	Plant Personnel.....	2-7.4
2-708	Truck Mixers.....	2-7.4
2-709	Preliminary Checks.....	2-7.4
2-710	Finishing Labor	2-7.5
2-711	Placing and Finishing Tools.....	2-7.5
2-712	Testing Equipment	2-7.6
2-713	Cold Weather Provisions	2-7.6
2-714	Subgrade.....	2-7.6

2-715	Subbase	2-7.6
2-716	Side Forms.....	2-7.7
2-716A	Reference Line.....	2-7.7
2-716B	Form Condition	2-7.7
2-716C	Bracing Pins.....	2-7.7
2-716D	Wooden Forms.....	2-7.8
2-716E	Sharp Curves	2-7.8
2-716F	Line and Grade	2-7.8
2-716G	Form Placement.....	2-7.8
2-716H	Longitudinal Joint Key.....	2-7.9
2-717	Slip-Form String Lines.....	2-7.10
2-717A	Normal String-Line Setting.....	2-7.10
2-717B	String-Line Transitions.....	2-7.10
2-717C	String-Line Repairs	2-7.11
2-718	Fine Grade	2-7.12
2-719	Joints	2-7.12
2-719A	Transverse.....	2-7.12
2-719B	Longitudinal	2-7.13
2-719C	Locating Transverse Joints.....	2-7.13
2-719D	Transverse Joint Construction.....	2-7.14
2-719E	Load Transfer Assemblies	2-7.16
2-719F	Dummy Joints.....	2-7.16
2-719G	Bulkheads	2-7.16
2-719H	Construction Joints	2-7.17
2-719I	Longitudinal Joint Construction	2-7.17
2-720	Paving Trains	2-7.18
2-720A	Side-Form Paving.....	2-7.18
2-720A.1	Initial Strike-off Spreader.....	2-7.19
2-720A.2	Transverse Finishing Machine	2-7.19
2-720B	Slip-Form Paving	2-7.19
2-720B.1	Spreader	2-7.19

2-720B.2	Paver.....	2-7.20
2-720C	Finishing Machines.....	2-7.20
2-720C.1	Longitudinal Float.....	2-7.20
2-720C.2	The Flex Plane Float.....	2-7.21
2-720C.3	The Chevron Float	2-7.21
2-720C.4	The Tube Float	2-7.21
2-720D	Tining Machine	2-7.21
2-721	Final Preparations for Placement of Concrete	2-7.21
2-722	Inspection Team	2-7.22
2-722A	Concrete Inspector	2-7.22
2-722B	Paving Inspector.....	2-7.22
2-722C	Finishing Inspector	2-7.22
2-723	Concrete Mix	2-7.23
2-723A	Mix Adjustments.....	2-7.23
2-723B	Consistency	2-7.23
2-723C	Slump Test.....	2-7.23
2-723D	Test Cylinders	2-7.24
2-724	Concrete Placement—Side-Form Paving	2-7.24
2-724A	Side-Form Placement of Lower Course.....	2-7.24
2-724B	Spreading	2-7.24
2-724C	Consolidation	2-7.25
2-724D	Placing Concrete Adjacent to Transverse Joints	2-7.25
2-724E	Reinforcement.....	2-7.26
2-724F	Side-Form Placement of Top Course	2-7.26
2-724G	Paving Adjacent Lanes	2-7.27
2-724G.1	Equipment Operation.....	2-7.27
2-724G.2	Longitudinal Joint.....	2-7.27
2-724H	Construction Joint.....	2-7.27
2-724I	Clean up	2-7.27
2-724J	Cold Weather.....	2-7.28
2-725	Concrete Placement—Slip-Form Paving	2-7.28

2-725A	Slip-Form Spreader Operation	2-7.28
2-725B	Slip-Form Paver Operations.....	2-7.29
2-725C	General Inspection.....	2-7.29
2-725D	Paver Speed	2-7.29
2-725E	Paver Movement.....	2-7.29
2-725F	Base Irregularities.....	2-7.29
2-725G	Mix Consistency and Quality.....	2-7.30
2-725H	Edge Slumping	2-7.30
2-725I	Consolidation.....	2-7.30
2-726	Finishing Pavement	2-7.30
2-726A	Hand Finishing	2-7.30
2-726B	Finishing Machine	2-7.31
2-726C	Longitudinal Floats	2-7.31
2-726C.1	The Longitudinal Float.....	2-7.32
2-726C.2	The Flex Plane Float	2-7.32
2-726C.3	The Chevron Float.....	2-7.32
2-726C.4	Tube Float.....	2-7.32
2-726D	Luting.....	2-7.33
2-726E	Joints	2-7.33
2-726E.1	Expansion Joints.....	2-7.33
2-726E.2	Construction Joints	2-7.34
2-726E.3	Transverse Joints	2-7.35
2-726F	Straightedging.....	2-7.35
2-726G	Tining.....	2-7.35
2-726H	Edging.....	2-7.36
2-727	Curing and Protection.....	2-7.36
2-727A	Moist Curing.....	2-7.36
2-727B	Curing Compound	2-7.37
2-727C	Polyethylene Cover Sheet Curing.....	2-7.37
2-728	Temporary Crossovers.....	2-7.38
2-729	Removing Forms	2-7.38

2-730	Sawing Longitudinal Joints	2-7.38
2-731	Sealing Joints	2-7.39
2-732	Daily Reports and Tests	2-7.39
2-733	Air Content.....	2-7.42
2-733A	Pressure Air Meter	2-7.42
2-733B	Chace Air Indicator.....	2-7.42
2-734	Pavement Cores	2-7.44
2-735	Opening the Pavement to Traffic.....	2-7.44
2-736	Full-Depth Concrete Pavement Replacement.....	2-7.44
2-736A	Concrete Removal.....	2-7.44
2-736B	Sawing.....	2-7.44
2-736C	Removal	2-7.45
2-736D	Existing Bituminous Patches.....	2-7.45
2-736E	Subbase	2-7.45
2-736F	Load Transfer	2-7.45
2-736G	Forms.....	2-7.46
2-736H	Reinforcement.....	2-7.46
2-736I	Placement and Finishing.....	2-7.46
2-736J	Consolidation	2-7.46
2-736K	Strike Off.....	2-7.46
2-736L	Surface Tolerances	2-7.47
2-736M	Joint Sealing	2-7.47
2-736N	Curing.....	2-7.47
2-736O	Testing	2-7.47
2-736P	Opening to Traffic.....	2-7.47

Chapter 8 - Structures

2-801	New Construction	2-8.1
2-802	Chief Inspector's Duties.....	2-8.1

2-803	Changes	2-8.1
2-804	Shop Drawings	2-8.2
2-805	Manufacturer's Supervision.....	2-8.3
2-806	Cofferdams and Underwater Concrete	2-8.3
2-807	Foundation Seals	2-8.4
2-808	Pumping.....	2-8.5
2-809	Removal of Cofferdams or Cribs	2-8.5
2-810	Stability of Foundations	2-8.5
2-811	Excavation	2-8.5
2-812	Tying New Concrete to Existing Concrete	2-8.5
2-813	Foundations	2-8.6
2-814	Spread Footings.....	2-8.6
2-815	Foundations Seated in Rock.....	2-8.7
2-816	Pile Supported Foundations	2-8.7
2-816A	Load Test	2-8.9
2-816B	Driving Plan.....	2-8.9
2-816C	Equipment.....	2-8.9
2-816D	Driving.....	2-8.10
2-816E	Tolerances.....	2-8.11
2-816F	Unacceptable Piles	2-8.11
2-816G	Reporting	2-8.11
2-817	Formwork	2-8.11
2-818	Reinforcement	2-8.12
2-818A	Plan Dimensions.....	2-8.12
2-818B	Cutting and Bending.....	2-8.12
2-818C	Storage	2-8.12
2-818D	Placement.....	2-8.12
2-818E	Splicing	2-8.13
2-818F	Epoxy Coating for Bars.....	2-8.14
2-819	Concrete.....	2-8.15
2-820	Concrete Mix	2-8.15

2-821	Sampling and Quality Control.....	2-8.15
2-821A	Sampling	2-8.15
2-821B	Testing	2-8.16
2-822	Placement	2-8.16
2-823	Construction Joints	2-8.17
2-824	Placing Concrete in Cold Weather.....	2-8.18
2-825	Curing.....	2-8.19
2-826	Finishing Concrete Surfaces.....	2-8.20
2-826A	Horizontal surfaces	2-8.20
2-826B	Sidewalks and Safety Curb.....	2-8.20
2-826C	Culvert Slabs	2-8.21
2-827	Superstructures.....	2-8.21
2-828	Steel Bridges	2-8.21
2-829	Box Girders	2-8.22
2-830	Temporary Bridges	2-8.22
2-831	Prestressed Bridges	2-8.22
2-832	Prestressed Superstructure	2-8.22
2-832A	Strength	2-8.22
2-832B	Camber	2-8.23
2-832C	Bering Areas.....	2-8.23
2-832D	Unacceptable Units	2-8.23
2-833	Girder Layout and Erection	2-8.23
2-834	Anchor Bolts and Bearings.....	2-8.23
2-835	Elastomeric Bearing Pads	2-8.24
2-835A	Materials.....	2-8.24
2-835B	Bearing Areas.....	2-8.25
2-835C	Installation.....	2-8.25
2-835D	Nonconforming Work	2-8.26
2-836	Pot Bearings or Disc Bearings.....	2-8.26
2-837	Expansion Dams	2-8.27
2-838	Steel Erection	2-8.29

2-839	Shear Connectors.....	2-8.29
2-840	Welding.....	2-8.29
2-841	Welder Qualifications.....	2-8.29
2-842	Inspection.....	2-8.29
2-842A	Weld Quality.....	2-8.30
2-842B	Defective Welds.....	2-8.30
2-843	Bolted Connections	2-8.31
2-844	Utility or Conduit Installation	2-8.31
2-845	Bridge Deck Procedures.....	2-8.31
2-846	Grades, Formwork and Screed Rails	2-8.31
2-847	Placing Concrete.....	2-8.32
2-848	Finishing	2-8.33
2-849	Joints	2-8.34
2-849A	Sealants	2-8.34
2-849B	Expansion Joint Material.....	2-8.35
2-849C	Systems and Devices.....	2-8.35
2-850	Protective Surface Treatment Compounds	2-8.36
2-851	Rehabilitation	2-8.37
2-852	General.....	2-8.37
2-853	Utilities	2-8.37
2-854	Bridge Deck Repair.....	2-8.38
2-855	Removal of Bituminous Wearing Surface	2-8.39
2-856	Location and Marking of Deteriorated Areas	2-8.40
2-857	Removal of Deteriorated Concrete	2-8.40
2-857A	Protective shields.....	2-8.40
2-857B	Removal by Pneumatic Hammer	2-8.41
2-857C	Removal by Hydrodemolition.....	2-8.42
2-858	Patching	2-8.43
2-858A	Preparations	2-8.43
2-858B	Spreading and Finishing.....	2-8.43
2-858C	Testing.....	2-8.44

2-858D	Unacceptable Work	2-8.44
2-858E	Opening To Traffic	2-8.44
2-859	Waterproofing Membrane.....	2-8.44
2-860	Placement of Bituminous Concrete Wearing Surface	2-8.44
2-861	Bridge Deck Joints	2-8.45
2-862	Structural Steel Inspection	2-8.45
2-863	Jacking.....	2-8.46
2-863A	Jacks and Beams	2-8.46
2-863B	Welding and Repairs	2-8.46
2-863C	Operations	2-8.46
2-864	Repair to Cover Plate Welds	2-8.47
2-865	Inspection of Structural Steel Cross Section	2-8.47
2-866	Heat Straightening Structural Members	2-8.48
2-867	Removal of Existing Bridge Decks	2-8.48
2-868	Protective Shields	2-8.48
2-869	Operations	2-8.48
2-870	Substructure Repairs	2-8.49
2-871	Deteriorated Concrete Removal	2-8.50
2-872	Repair Materials.....	2-8.50
2-873	General Repair Requirements.....	2-8.50
2-874	Shotcrete.....	2-8.50
2-874A	Equipment	2-8.51
2-874B	Preparatory Work	2-8.51
2-874C	Application.....	2-8.51
2-875	Copolymer Cementitious Mortar.....	2-8.52
2-876	Crack Repair by Epoxy Injection	2-8.52
2-877	Painting	2-8.53
2-878	Preconstruction Requirements.....	2-8.53
2-879	Debris and Material Storage	2-8.53
2-880	Containment System.....	2-8.53
2-880A	Containment Plan.....	2-8.53

2-880B	Containment Meeting.....	2-8.54
2-881	Equipment.....	2-8.54
2-882	Cleaning Inspection.....	2-8.55
2-883	Containment Enclosures.....	2-8.55
2-884	Air Pressure in Containment Enclosures	2-8.56
2-885	Surface Preparation	2-8.56
2-886	Waste Disposal	2-8.57
2-887	Coatings Inspection	2-8.57
2-888	Materials	2-8.57
2-889	Weather	2-8.58
2-890	General Requirements.....	2-8.58
2-891	Coating New Steel.....	2-8.58
2-892	Coating Existing Steel.....	2-8.58
2-893	Defective Work.....	2-8.59
2-894	Stenciling	2-8.59
2-895	Paint Storage.....	2-8.59
2-896	Health and Safety	2-8.60
2-897	Reporting	2-8.60

Chapter 9 - Construction Traffic

2-901	Public Relations.....	2-9.1
2-902	Press Releases.....	2-9.1
2-903	Daily Traffic Reports.....	2-9.1
2-904	Weekly Traffic Reports.....	2-9.2
2-905	Specifications	2-9.2
2-906	Maintenance and Protection of Traffic	2-9.2
2-907	General.....	2-9.2
2-908	Payment	2-9.2
2-909	Contractor Nonperformance	2-9.3

2-910	Public Safety	2-9.3
2-911	Potholes	2-9.3
2-912	Roadway Trenches	2-9.4
2-913	Low Bridge Clearance	2-9.4
2-914	Storage of Equipment and Material.....	2-9.4
2-915	Removal and Reinstallation of Rail Systems	2-9.4
2-916	Limitation of Operations.....	2-9.4
2-917	Requests for Changes	2-9.5
2-918	Expressway Projects	2-9.5
2-919	Inspection	2-9.5
2-920	Liquidated Damages	2-9.6
2-921	Speed Limits	2-9.6
2-922	Business Access	2-9.7
2-923	Traffic Control Patterns	2-9.7
2-924	Temporary Patterns	2-9.8
2-925	Permanent Patterns	2-9.8
2-926	Detours	2-9.9
2-927	Night Patterns.....	2-9.9
2-928	Adjustments	2-9.9
2-929	Tapers	2-9.10
2-930	Buffer Space.....	2-9.10
2-931	Sign Placement.....	2-9.10
2-932	Inspection Responsibilities	2-9.11
2-933	General Inspection	2-9.11
2-934	Traffic Flow.....	2-9.12
2-935	Lane Closures.....	2-9.12
2-936	Detours	2-9.12
2-937	Detour of a State Highway to a Town Road.....	2-9.13
2-938	Detour of a State Highway to Another State Highway	2-9.13
2-939	Detour of a Town Road to Another Town Road.....	2-9.13
2-940	Temporary Detours	2-9.13

2-941	Detour Operations	2-9.14
2-942	Construction Signs	2-9.14
2-943	Signs	2-9.14
2-944	Barricade Warning Lights	2-9.14
2-945	Extended Shutdowns	2-9.15
2-946	Ordering	2-9.15
2-947	Placement.....	2-9.15
2-948	16-Series Signs	2-9.15
2-949	Inspection.....	2-9.16
2-950	Changeable Message Signs	2-9.16
2-951	Portable Signs.....	2-9.16
2-952	Permanent Signs	2-9.17
2-953	Arrow Boards	2-9.18
2-954	Channelizing Devices.....	2-9.18
2-954A	Barricades	2-9.18
2-954B	Temporary Precast Concrete Barrier Curb	2-9.18
2-954C	Installation	2-9.19
2-954D	Taper Lengths	2-9.19
2-954E	Delineation	2-9.20
2-954F	Attachment	2-9.21
2-954G	End Treatments.....	2-9.21
2-955	Component Inspection	2-9.21
2-956	Payment for TPCBC.....	2-9.22
2-957	Impact Attenuation Modules (Sand Barrels)	2-9.23
2-958	One-Meter Traffic Cones	2-9.23
2-959	Traffic Drums	2-9.24
2-960	Pavement Markings.....	2-9.24
2-960A	Painted Markings.....	2-9.25
2-960B	Plastic Markings.....	2-9.25
2-960C	Marking Removal.....	2-9.25
2-961	Portable Impact Attenuator Systems (Crash Trucks)	2-9.25

2-961A	Use.....	2-9.25
2-961B	Inspection	2-9.26
2-962	Trafficmen.....	2-9.26
2-962A	General	2-9.26
2-962B	State Police Officers.....	2-9.27
2-962C	Town or City Police Officers or Uniformed Trafficmen.....	2-9.27
2-962D	Prior Approval.....	2-9.27
2-962E	Work Control.....	2-9.27
2-962F	Operations	2-9.28
2-962G	Documentation.....	2-9.28
2-962H	Payment.....	2-9.29

Chapter 10 - Miscellaneous Construction

2-1001	Riprap.....	2-10.1
2-1002	Gabions	2-10.1
2-1003	Wire Fence	2-10.3
2-1004	Wood Posts.....	2-10.3
2-1005	Metal Posts.....	2-10.3
2-1006	End, Corner and Pull Posts	2-10.4
2-1007	Metal Beam Rail	2-10.4
2-1008	Material Inspection	2-10.5
2-1009	Posts	2-10.5
2-1010	Rail	2-10.5
2-1011	Welding	2-10.5
2-1012	Anchorages.....	2-10.6
2-1013	Turf Establishment.....	2-10.6
2-1014	Seedbed Preparation	2-10.6
2-1015	Seeding and Fertilizing.....	2-10.7
2-1016	Establishment and Cleanup	2-10.7

2-1017	Erosion Control Matting	2-10.7
2-1018	Sodding	2-10.7
2-1019	Ground Preparation	2-10.8
2-1020	Planting	2-10.8
2-1021	Pegging	2-10.8
2-1022	Finishing and Maintenance	2-10.8

List of Figures

Chapter 1 - Environmental Protection

2-1.1	Administrative Memorandum No. 97—Environmental Compliance.....	2-1.4
2-1.2	24-Hour Rule Form	2-1.17
2-1.3	Environmental Checklist—New Project Startup.....	2-1.21
2-1.4	Project Site Environmental Inspection Report	2-1.22

Chapter 2 - Construction Surveys

2-2.1	Typical Offset Stake Markings.....	2-2.9
2-2.2	Recommended Stake Standards	2-2.10

Chapter 3 - Excavation and Embankment

2-3.1	Illustration of Lines and Limits.....	2-3.2
2-3.2	Setting Slope Stakes	2-3.3
2-3.3	Signs for Blasting	2-3.9
2-3.4	Disposal of Unsuitable Material	2-3.13
2-3.5	Data and Computation Sheet for Nuclear Field Density Tests (Form CON-125).....	2-3.20
2-3.6	Department of Public Utility Control—Incident Report Form	2-3.23

Chapter 4 - Drainage

2-4.1	Paved Invert.....	2-4.5
2-4.2	Certification of Precast Concrete Products (Form PC-1).....	2-4.9
2-4.3	Endwall Layout	2-4.11
2-4.4	Pipe Installation with Gravel Fill	2-4.13
2-4.5	Pipe Installation without Gravel Fill.....	2-4.14
2-4.6	Catch Basin (Type CL).....	2-4.18

2-4.7	Underdrain	2-4.20
-------	------------------	--------

Chapter 5 - Base Courses

2-5.1	Base & Bituminous Concrete Inspection Report (Form CON-136)	2-5.3
2-5.2	Avoiding Water Entrapment	2-5.5

Chapter 6 - Bituminous Pavements

2-6.2	Typical Bituminous Paver—Side View and Top View	2-6.4
2-6.3	Screed Details	2-6.6
2-6.4	Paver Leveling Action	2-6.7
2-6.5	Tire Arrangement—Pneumatic-Tire Rollers	2-6.8
2-6.6	Typical Material Transfer Device (MTD).....	2-6.9
2-6.7	Prepaving Meeting Agenda.....	2-6.11
2-6.8	Preferred Truck Loading Sequence	2-6.15
2-6.9	Spray Bar Overlaps.....	2-6.16
2-6.10	Incorrect Spray Bar Overlaps	2-6.16
2-6.11	Factors That Influence the Vertical Position of the Screed	2-6.18
2-6.12	Angle of Attack—Manual or Automatic Control of Tow Points	2-6.18
2-6.13	Correct Head of Material Volume	2-6.19
2-6.14	Head of Material—Volume Too High	2-6.19
2-6.15	Head of Material—Volume Too Low.....	2-6.20
2-6.16	Mat Trouble Shooting Guide	2-6.22
2-6.17	Example Paving Layout.....	2-6.34
2-6.18	Rolling Patterns.....	2-6.37
2-6.19	Nuclear Density Tests (Sample).....	2-6.40
2-6.20	Permanent Transition Keyway	2-6.42
2-6.21	Permanent Transition Dimensions.....	2-6.42
2-6.22	Construction of a Day Joint	2-6.43
2-6.23	Temporary Transition Tapers.....	2-6.44
2-6.24	Starting Blocks.....	2-6.44

2-6.25	Final Pavement Evaluation Report	2-6.48
2-6.26	Weekly HMA Production Report.....	2-6.42
2-6.27	Base & Bituminous Inspection Report (Form CON-136)	2-6.52
2-6.28	Adjustment Schedule for Bituminous Concrete Form	2-6.57
2-6.29	Liquid Asphalt Adjustment Form	2-6.60
2-6.30	Leveling and Wedging Examples	2-6.64

Chapter 7 - Concrete Pavements

2-7.1	Mix Design	2-7.2
2-7.2	Layout to Avoid a Featheredge	2-7.9
2-7.3	String-Line Stakes	2-7.11
2-7.4	Transverse Joint Layout	2-7.13
2-7.5	Pressure Relief Joint.....	2-7.14
2-7.6	Expansion Joint	2-7.15
2-7.7	Contraction Joint	2-7.15
2-7.8	Longitudinal Joint.....	2-7.17
2-7.9	Concrete Pavement Daily Inspection Report (Form CON-135).....	2-7.40

Chapter 8 - Structures

2-8.1	Foundation Seal	2-8.4
2-8.2	Piles.....	2-8.8
2-8.3	Pile Driving Record (Form CON-87)	2-8.60
2-8.4	Mortar Block	2-8.14
2-8.5	Construction Joint.....	2-8.18
2-8.6	Shear Connectors.....	2-8.21
2-8.7	Elastomeric Bearing Pad Assembly	2-8.25
2-8.8	Pot Bearing	2-8.26
2-8.9	Rocker Setting	2-8.28

2-8.10	Weld Quality Factors	2-8-.30
2-8.11	Bolt Head Markings.....	2-8.70
2-8.12	Poured Joint Seal.....	2-8.34
2-8.13	Box Seal Expansion Joint System	2-8.36
2-8.14	Strip Seal Joint Device.....	2-8.36
2-8.15	Bridge Deck Repair	2-8.39

Chapter 9 - Construction Traffic

2-9.1	Characteristics of Operating Guide Rail	2-9.29
2-9.2	Characteristics of Median Barriers.....	2-9.30
2-9.3	Request for Change to Contract Traffic Specifications	2-9.31
2-9.4	Traffic Control Plan 1—Work in Right Lane—Multilane Highway	2-9.43
2-9.5	Traffic Control Plan 2—Work in Right Two Lanes—Multilane Highway	2-9.44
2-9.6	Traffic Control Plan 3—Work in Left Lane—Multilane Highway	2-9.45
2-9.7	Traffic Control Plan 4—Work in Left Two Lanes—Multilane Highway	2-9.46
2-9.8	Traffic Control Plan 5—Work in Left and Center Lane— Multilane Highway (Utilizing Shoulder)	2-9.47
2-9.9	Traffic Control Plan 6—Work in Shoulder Area—Multilane Highway.....	2-9.48
2-9.10	Traffic Control Plan 7—Work in Ramp Gore Area	2-9.49
2-9.11	Traffic Control Plan 8—Typical Ramp Treatments for Mainline Lane Closure—Multilane Highway	2-9.50
2-9.12	Traffic Control Plan 9—Work on Turning Roadways/Ramps.....	2-9.51
2-9.13	Traffic Control Plan 10—Work in Right Lane—Four-Lane Undivided Highway.....	2-9.42
2-9.14	Traffic Control Plan 11—Work in Left Lane—Four-Lane Undivided Highway.....	2-9.53
2-9.15	Traffic Control Plan 12—Work in Both Lanes—Four-Lane Undivided Highway.....	2-9.54
2-9.16	Traffic Control Plan 13—Work in Travel Lane and Shoulder—Two-Lane Highway—Alternating One-Way Traffic Operations	2-9.55
2-9.17	Traffic Control Plan 14—Work in Shoulder—Two-Lane Highway	2-9.57

2-9.18	Traffic Control Plan 15—Work in Travel Lane and Shoulder—Two-Lane Highway	2-9.58
2-9.19	Traffic Control Plan 16—Work in Middle of Roadway—Two-Lane Highway	2-9.59
2-9.20	Traffic Control Plan 17—Work in Middle of Roadway at Intersection.....	2-9.60
2-9.21	Traffic Control Plan 18—Work in Travel Lane and Shoulder—Two Lane Highway— Alternating One-Way Traffic Operation—Stop Sign Control	2-9.61
2-9.22	Traffic Control Plan 19—Moving Operation on Right Shoulder—Multilane Highway and Secondary Roadways.....	2-9.62
2-9.23	Traffic Control Plan 20—Moving Operation in Right Lane and Outside Shoulder at the Same Time—Multilane Highway	2-9.63
2-9.24	Traffic Control Plan 21—Moving Operation in Left Lane and Inside Shoulder at the Same Time—Multilane Highway.....	2-9.64
2-9.25	Traffic Control Plan 22—Moving Operation in Center Lane—Multilane Highway.....	2-9.65
2-9.26	Traffic Control Plan 23—Moving Operation in Center Lane—Multilane Highway.....	2-9.66
2-9.27	Traffic Control Plan 24—Moving Operation—Two-Lane Highway.....	2-9.67
2-9.28	Traffic Control Plan 25—Moving Operation—Multilane Highway	2-9.68
2-9.29	Traffic Control Plan 26—Series 16 Signs	2-9.41
2-9.30	Traffic Control Plan Notes (Construction)	2-9.42
2-9.32	Traffic Control Plan—H.O.V. Plan 1—Work in Restricted Lane (Stationary Closure).....	2-9.69
2-9.33	Traffic Control Plan—H.O.V. Plan 2—Work in Separator of Restricted Lane (Stationary Closure)	2-9.70
2-9.34	Traffic Control Plan—H.O.V. Plan 3—Work in Left Shoulder of Restricted Lane (Stationary Closure)	2-9.71
2-9.35	Traffic Control Plan—H.O.V. Plan 4—Moving Operation in Restricted Lane.....	2-9.72

2-9.38	Terms for Work Zone Traffic Control Patterns	2-9.8
2-9.39	Temporary Precast Concrete Median Barrier Curb	2-9.19
2-9.40	Typical Temporary Precast Concrete Barrier Curb Installation.....	2-9.20
2-9.41	Connection Assembly for Temporary Precast Concrete Barrier Curb	2-9.22
2-9.42	Traffic Cone	2-9.24
2-9.43	Traffic Drum	2-9.24

Chapter 10 - Miscellaneous Construction

2-10.1	Gabion Field Assembly	2-10.2
2-10.2	Gabion Placement	2-10.2
2-10.3	Gabion Connecting Wires.....	2-10.3
2-10.4	Wire Fence Pull Post.....	2-10.4
2-10.5	Metal Beam Guardrail Anchorage.....	2-10.6